

# अखिल भारतीय आयुर्विज्ञान संस्थान, नागपुर

ALL INDIA INSTITUTE OF MEDICAL SCIENCES, NAGPUR

Plot No - 2, Sector - 20, MIHAN, Nagpur- 441108

Email ID: - [se@aiimsnagpur.edu.in](mailto:se@aiimsnagpur.edu.in), [eecivil@aiimsnagpur.edu.in](mailto:eecivil@aiimsnagpur.edu.in)

## ENGINEERING DEPARTMENT



AIIMS/NAG/ENGG/CIVIL/NIQ/Cistern repair/26-27/१५

Date: - 25/08/2026

### NOTICE INVITING QUOTATION

The Executive Director AIIMS Nagpur invites sealed quotation for "**Demolishing existing concealed cistern and Repair/Installation of new cistern required all civil works and finishing with Grill Provision in various floors of IPD Building at AIIMS Nagpur**" from the vendors having similar kind of work experience

NIQ No. : - AIIMS/NAG/ENGG/CIVIL/NIQ/ Cistern repair /26-27/ १५

### Schedule of Quantities

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                         | Quantity | Unit | Unit Rate | Amount (₹) |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------|------------|
| 1       | Demolishing R.C.C. work / granite manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 meters lead as per direction of Engineer - in- charge.                                                                                                    | 8.00     | Cum  |           |            |
| 2       | Dismantling dressed stone work ashlar face stone work, granite work, marble work or precast concrete work manually/ by mechanical means including stacking of serviceable and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge : In cement mortar cum        | 8.00     | Cum  |           |            |
| 3       | Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved | 16       | Cum  |           |            |
| 4       | Dismantling of flushing cistern of all types (C.I./PVC/Vitreous China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 meters lead.                                                                                                                  | 100      | each |           |            |
| 5       | Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 litre capacity - White ((Make - Hindware or equivalent with warranty of 12 months minimum)                                       | 100      | each |           |            |
| 6       | 15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand)                                                                                                                                                                                                    | 54       | Sqm  |           |            |
|         | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and                                                                                                                                                                                                            | 54       | Sqm  |           |            |

|                                |                                                                                                                                                                                                                                                                                                                 |    |     |  |  |
|--------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-----|--|--|
|                                | manufacturer, over the plastered wall surface to prepare the surface even and smooth complete                                                                                                                                                                                                                   |    |     |  |  |
| 8                              | Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour (Two Coat)                                                     | 54 | Sqm |  |  |
| 9                              | Providing and fixing expanded metal 20x60 mm strands 3.25 mm wide and 1.6 mm thick for windows etc. including 62 x19 mm beading of Aluminium / galvanized steel section( this item will be fixed on granite by screw for enclosing the toilet sheet fixed and the same should be openable for easy maintenance) | 50 | Sqm |  |  |
| GST Amount (Considering 18 %)  |                                                                                                                                                                                                                                                                                                                 |    |     |  |  |
| Total Amount including GST (₹) |                                                                                                                                                                                                                                                                                                                 |    |     |  |  |

#### **Terms & Conditions of NIQ:**

- 1) All quotation to be submitted in the name of Executive Director, AIIMS Nagpur only. Quotation not addressed to the Executive Director, AIIMS Nagpur will not be opened & rejected.
- 2) The work shall be completed within **45 Days** from the date of issue of work order.
- 3) The work shall be carried out as per specification and as per direction of Engineer-in-charge.
- 4) All material, labour and machineries shall be arranged by the agency himself at own cost.
- 5) Rate of items should be quoted per unit item excluding GST & GST should be mentioned in GST row separately & all applicable Taxes and nothing extra shall be paid on this account.
- 6) The vendors should submit quotation in uploaded NIQ or firm's letter head as per format form duly signed & stamped.
- 7) Bank details such as Account Number, IFSC code etc. should be furnished so as to facilitate payment online.
- 8) Payment shall be made to firm after completion of work.
- 9) It will be deemed that work so measured, checked and paid is of the required quality and standard, both in respect of ingredients as well as the intended functions it is supposed to perform. In other words, the work shall not only meet the required / CPWD specifications but also the workmanship as per sound engineering practices.
- 10) Liquidated damages charges: - In the event of the delayed completion of work within stipulated period, Liquidated damage charges will be deducted to the sum of 0.5 % the contract amount of the delayed / undelivered, stores /services mentioned above for every week of delay or part their of a week, subject to the maximum value of the liquidated damages being not higher than 10 % of the value of delayed services.
- 11) Interested parties should submit their quotation through hard copy Administrative building of AIIMS Nagpur scribing **"Demolishing existing concealed cistern and Repair/Installation of new cistern required all civil works and finishing with grill provision in various floors of IPD"**

**Building at AIIMS Nagpur."** on or before 03 Sep 2026 before 13:00 hrs, quotations will be opened on 03 Sep 2026 at 15:00 hrs.

- 12) The Firm is requested to visit the site to understand the actual condition of site / location. If any material to be transported, the cost shall be borne by the firm.
- 13) Firm to quote item wise rates. Evaluation will be total value wise. The work will be awarded to the lowest (L1) eligible vendor.
- 14) If any damaged occurred during execution, transportation the same shall be repaired or make Good by the vendor.
- 15) The work shall be completely carried out as per the description of each item with material of approved make and quality and as approved by the Engineer in charge.
- 16) Right to accept /reject any quotation rest with the AIIMS, Nagpur.
- 17) List of mandatory documents to be filled in by the vendor in various forms and submit the same with quotation within the period of bid submission.
  - i) Bidder details as per Annexure A.
  - ii) GST Registration Certificate.
  - iii) Copy of Signed NIQ

  
Superintending Engineer  
AIIMS Nagpur  
ले. कर्नल निखिल बी. पांडे  
Lt. Col Nikhil B. Pandey  
अधीक्षक अभियंता  
Superintending Engineer  
अखिल भारतीय आयुर्विज्ञान संस्थान  
All India Institute of Medical Sciences  
नागपुर - 441108  
Nagpur - 441108